

SPECIFICATIONS FOR EVT0001709

Gutter Replacement for Bldg 1460
Camp Funston, Fort Riley, Kansas

Fort Riley MATES

The gutters on Building 1460 at Camp Funston, Fort Riley, Kansas, have rusted through and need to be removed and replaced by the contractor.

The scope of work is as follows:

1. Remove existing materials called out for replacement in this bid event.
2. Replace existing 24 gauge galvanized gutters with 24 gauge galvanized gutters.
3. Replace existing 4" X 5" corrugated galvanized downspouts with 4" by 5" corrugated galvanized downspouts.
4. Replace existing gutter expansion joints and strainers at the downspouts.
5. Replace 1 – 4"X4" Missing downspout on the "STAR" Building.
6. A two year contractor warranty is preferred.
7. Bid should include all material and labor charges.
8. Bid should include taxes for all materials incorporated into project.

POC is Wally Wolfe at 785-239-0986 or waldon.wolfe@us.army.mil.