

## **Engineer's Estimate of Quantities – EVT0001849**

### **Kansas Department of Wildlife, Parks and Tourism**

#### **Milford Wildlife Area – 13<sup>th</sup> Street Bridge Replacement Milford State Park**

#### **Engineer's Estimate of Quantities**

---

The following quantities are approximate and provided for contractor bid information purposes only. Contractor shall verify quantities prior to bidding. All miscellaneous items necessary to complete the bid item are considered subsidiary to the bid item.

No.	Item	Quantity	Unit
1	Mobilization	1	LS
2	Clearing and Grubbing	1	LS
3	Demolition	1	LS
4	Seeding and Mulching	1	LS
5	Benchmark	2	EA
6	Compacted Fill	1	LS
7	Unclassified Excavation	1	LS
8	Compacted Road Rock	215	SY
9	Contech Aluminum Box Culvert (#32)	22.5	LF
10	Aluminum Headwalls	2	EA
11	Aluminum Wingwalls	2	EA
12	Culvert Footing	45	LF
13	Single W-Beam Guardrail	140	LF
14	18" Nom. Dia. RipRap w/ nonwoven geotextile fabric under	72	SY
15	Propex 300 Turf Reinforcement Matting	65	SY
16	Erosion Control Blanket	159	SY
17	Traffic Control	1	EA