

Beloit Salt/sand Building

The purpose of this work is to provide labor and equipment to construct the concrete footings and walls for the Beloit salt/sand bunker at 721 North Independence Avenue, Beloit, KS.. A drawing of the structure with dimensions is attached.

Footings:

The footings are 3'x3' and will be dug by KDOT forces. KDOT forces will provide and place the reinforcing steel in the footings.

The contractor will help square the footing and help place and finish the concrete and install the vertical steel that ties into the walls.

KDOT will provide labor to help with the concrete placement.

KDOT will order and pay for the concrete.

Walls:

The wall forms shall be provided, set and removed by the contractor. Care shall be taken to make certain they are plumb, square, and will not blow out during the concrete placement.

KDOT will provide labor to help place the reinforcing steel for the walls.

The contractor shall be responsible for providing a pump truck or other suitable, preapproved method of concrete placement. If something other than a pump truck is used, approval must be obtained from Leland Tice, Area 2 Engineer prior to use.

The contractor will be responsible for concrete placement and finishing. KDOT will provide labor to help with the concrete placement and finishing.

The concrete shall be consolidated with concrete vibrators provided by the contractor so that honeycombing does not occur.

Forms shall stay in place for 48 hours minimum after the concrete placement.

KDOT will order and pay for the concrete.

